



Ensuring Comparable Access with PROMOD

Models Used in Analysis

- 2012 Summer Peak Load Level
- 80% of 2012 Summer Peak Load Level
- 60% of 2012 Summer Peak Load Level

Transaction Directions

Transactions were evaluated from all Source Subsystems to all Sink Subsystems

■ Source Subsystems

- CE (1800 MW)
- NSP (598 MW)
- ALTW (530 MW)
- DPC (55 MW)
- ALTE
- WE
- WPS
- MGE
- UPPC

■ Sink Subsystems

- ALTE (1800 MW)
- WE (1800 MW)
- WPS (1065 MW)
- MGE (441 MW)
- UPPC (58 MW)
- WPPI Load (307 MW)
- MPU (87 MW)
- Edison Sault (46 MW)

Monitored and Contingent Elements

- Monitored Elements
 - All ATC Facilities 69 kV up to 345 kV
 - All External Facilities 69 kV and up
- Contingent Elements
 - All single contingencies within all Source Subsystems were taken.